

SEYMOUR STREET, LISBURN

SECANT WALL



Description:

Quinn Piling installed a 112m long retaining wall with secant piles at 600mm diameter.

Along with the secant wall installation a second Quinn Piling rig installed 450 diameter, 17m long bearing piles.

As this site bordered on sensitive and occupied buildings a Quinn Piling vibration monitor was installed for the duration of the piling works.

Title: Apartments, Seymour Street, Lisburn

Contractor: Sean Devine

Engineer: Albert Fry

